BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Satellite Town Sub Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
BBMP, Bangalore

Approved Tender SCHEDULE –'B'

Name of Woradk:-Modified schedule-B Providing and asphalting to balance road and providing and laying pipeline in Chitra layout in Attur ward no-03 of Ynk Satellite Town Sub Division

Sl.No	Description of work	Unit	Approved Qty	Rate quoted by the contractor Technical Manager (west) KRIDL, BBMP	
				Rate	Rate in words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	121.44	76.00	Rupees seventy six only
2	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130, PWD SR 2014-15)	Cum	121.44	69.00	Rupees sixty nine only

3	KSRRBM400-17, Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site,laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired dencity complete as per specifications. MORTH Specification No.406(Item no20.18,Page no154,PWD SR 2014-15)	Cum	102.30	1500.00	Rupees one thousand five hundred only
4	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	1364.00	36.00	Rupees thirty six only
5	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment, rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethe desired compactionasperMORTHSpecificationclauseno508completeinallrespectscomplete asperspecifications.using100120THcapacityH.M.P with sensor paver gradingI(35-40mm)with4.5%CRMB55grade(Itemno21.21.1,Pageno16D 2014-15)	Cum	54.56	11000.00	Rupees eleven thousand only
6	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in **hard soil** not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, **No. 5/ Item No. 2.4/ PWD SR 2014-15**	Cum	243.00	259.70	Rupees two hundred fifty nine and paise seventy only

7	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.3 item No.4.2 **PRE SR2014-15.**	Rmtr	900.00	116.00	Rupees one hundred sixteen only
8	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications, **No. 6/ Item No. 2.11/ PWD SR 2014-15**	Cum	243.00	69.96	Rupees sixty nine and paise ninety six only
9	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **50mm** nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 (P.89/I.13.37 **PWD SR - 2014-15)**	Each	20.00	2120.00	Rupees two thousand one hundred twety only

Signatur of the contractor

Executive Engineer
Yelahanka Division
BBMP, Bangalore

ಮೇಜರ್ ಸಂದೀಪ್ ಉನ್ನಿಕೃಷ್ಣನ್ ರಸ್ತೆ,

ಟಪ್ಪಣಿಗಳು ಮತ್ತು ಆಜ್ಞೆಗಳು